

BRADLEY SAND & CONCRETE CRUSHING, LLC

*P.O. BOX 76, SANTA FE, TX 77517 * (409) 370-3950*

October 5, 2023

Quote Number: 10052301

Quote To:

Brazoria County Engineering
111 E. Locust, Room 303
Angleton, TX 77515

Location:

Savannah Parkway Repair

Item	Amount
Mobilization	\$ 10,000.00
Demo and removal of Concrete Road Area (4500 SF)	\$ 8,750.00
Remove 6" of Subgrade (85 CY)	\$ 4,500.00
Place 12" of Stabilized Sand in repair area (170 Yds)	\$ 8,500.00
Form and pour 8" 4000 PSI Concrete (120 CY)	\$ 23,700.00
Traffic Control	\$ 3,050.00
Total	\$ 58,500.00

Description of Work:

Demo, Repair Subgrade and pour 8" of 4000 PSI concrete and Curbs that is collapsing on Savannah Parkway a pedestrian crossing tunnel. 120 LF on the North Bound Lanes and 60 LF on the South Bound Lanes.

Note:

This price includes all necessary traffic control requirements as per county standards.

Reviewed and Approved by _____

Date _____

BRADLEY SAND & CONCRETE CRUSHING, LLC

*P.O. BOX 76, SANTA FE, TX 77517 * (409) 370-3950*
