



Proposal

Date: April 21, 2026

Cloudt Construction

(281) 331-1776

Chris Cloudt

(832)465-0901

Customer: Fuentes

Site Address 9810 CR 200

Alvin, TX

Jurisdiction: Brazoria County

Description of Work	Unit Price	Line Total
Install ProFlo 500 GPD Aerobic Treatment Unit, design, permit, tie-in to home (sch40), electrical to meter pole, pump and controls (mounted on the tank), spray field, sand for backfill, liquid chlorinator, etc., for a 3 or 4 bedroom home, installed per design specifications. (Residential System).	Materials	\$ 7,250.00
Notes:		-
1) Any changes or variations to the system from the above written description may result in price changes.		
2) 30 amp service required (provided at the meter pole). Electrical from main panel to tank is INCLUDED in this proposal.	Labor	4,500.00
3) Annual BOD testing is required for commercial systems and will be completed at the cost of the homeowner (\$250 generally)		-
4) 2 year warranty on parts/labor and first 2 years of maintenance included. Does not include damage to the system by owner, e.g. broken spray heads, ants, etc.		-
6) Approved permits expire after 12 months. If they expire, it will require a new permit fee at the owner's expense.		
7) Mats, if needed, for tank delivery are NOT included in this proposal (only needed in case of very wet ground)		
8) Not responsible for any underground lines that are not marked prior to job start.		
9) Old tank pumpout cost is INCLUDED in this proposal.		
10) Proposal good for 30 days.		
		-
	Subtotal	\$ 11,750.00
		-
	Total	\$ 11,750.00

Make Checks Payable to Cloudt Construction

Customer Signature

Date